





Beam Plan Scale 1:100

Beam						
POS	PRO	n	L	SUM L	KG/M	SUM W
1	INP18	3	4.900	14.700	19.100	280.770
2	INP18	3	3.050	9.150	19.100	174.765
3	INP18	3	2.700	8.100	19.100	154.710
4	INP18	3	2.900	8.700	19.100	166.170
5	INP18	3	3.750	11.250	19.100	214.875
6	INP20	16	4.600	73.600	26.200	1928.320
7	INP20	12	4.800	57.600	26.200	1509.120
8	INP20	2	2.700	5.400	26.200	141.480

Total W = 4570.210